	t of agricultural fields on Erven 1372 and 1375,			Nature of Impact			Without Mitigation (Baseline)					Without With Mitigation					With Mitigation	Short Description of som
ENVIRONMENTAL RATING SIGNIFICANCE KEY			Number	Aspect	Impact	Probability (Likelihood)	Extent	Duration (Frequency)	Magnitude (Intensity/ Severity)	Receiving Environment (Consequence)		Probability (Likelihood)	Extent	Duration (Frequency)	Magnitude (Intensity/ Severity)	Receiving Environment (Consequence)	Score (Impact Assessment)	Mitigation Measures / Enhancement Measures
									CON	TRUCTION PHAS	E		•					
SIGNIFICANCE	RATING	Final rating score / value range	1	Groundwater	Pollution	0	0	0	0	0	0	0	0	0	0	0	0	
Very Significant	Very High	>11 to -16	2		Insufficient number of toilets and / or inappropriate disposal of sewage generated during the construction phase.	-4	-1	-3	-2	-2	3	-1	-1	-3	-1	-1	-2	Provide sufficient number of toilets for constrution phase workers
Significant Increasing Significance Insignificant Significant	High Medium Low Very Low RATING	>-4 to -7 -2 to -4 -1 to <-2 Final rating score / value range	3	Waste	Temporary increase in waste and litter	-6	-1	-3	-5	-3	4	-2	-1	-1	-1	-1	-2	Provide an environmental awareness presentation before construction work is commenced with and hold construction supervisor responsible for adherence.
Significant Increasing Significant Insignificant		10 to 16 4 to <10 1 to <4	4		Clearance of indigenous vegetation	-2	7	-1	-1	-3	-2	-1	-1	-1	-1	-1	-1	Keep construction work strictly within the 1ha expansion footprint
			5		Protected & endangered plant species: Potential impact on threatened or protected	-7	-1	-5	-7	-5	-5	-1	-1	-1	-1	-1	-1	Obtain permits to disturb protected plants and fence indigenous tree patch
			6		Conservation priority: Potential impact on protected areas, CBAs, ESAs or Centres of Endemism.	0	0	0	0	0	0	0	0	0	0	0	0	
			7	Biodiversity	Connectivity: Potential loss of ecological migration corridors.	0	0	0	0	0	0	0	0	0	0	0	0	
			8		Encroachment of alien invasive vegetation in disturbed areas during construction activities	0	0	0	0	0	0	0	0	0	0	0	0	
			9		Veld fire risk: Potential risk of veld fires as a result of construction workers trying to warm themselves using fire.	-5	-1	-4	-5	-5	-4	-2	-2	-1	-1	-3	-2	No fires must be allowed of the site
			10	İ	Cumulative impacts: Cumulative impact associated with proposed activity.	-2	-1	-1	-1	-1	-2	-1	-1	-1	-1	-1	-1	Keep to all the mitigation measures suggested above and below.
			11		The "No-Go" option: Potential impact associated with the No-Go alternative.	0	0	0	0	0	0	0	0	0	0	0	0	
			12	Services	Increase in demand for municipal services (i.e. increased demand for water, electricity, sewage disposal and solid waste disposal).	0	0	0	0	0	0	0	0	0	0	0	0	
			13	Impact on Cultural, Archaeological Palaeontological, and Heritage	Artefacts may be discovered and/or damaged during the construction phase.	-3	-1	-3	-3	-3	-3	-2	-2	-1	-1	-1	-2	Obtain authorisation from SAHRA before clearing the site middens of medium significance.
			14		Loss and/or damage to potential fossils and archaeological and historical sites within the construction footbrint	-3	-1	-3	-3	-3	-3	-2	-2	-1	-1	-1	-2	
			15	Socio-economic	Creation of short-term employment opportunities during the construction chase.	3	3	3	3	3	3	3	3	3	3	3	3	
			16	Dust	Dust will be generated during the construction phase of the proposed development which may impact drivers and commuters.	-2	-1	-1	-1	-1	-2	-1	-1	-1	-1	-1	-1	Spray water when dust is generated
			17	Visual	Site may look out of place in the surrounding environment as a result of the development proposal	0	0	0	0	0	0	0	0	0	0	0	0	N/A
			18	Noise	Noise will be generated during the construction phase.	-4	-2	-1	-3	-2	-3	-3	-2	-1	-2	-1	-2	Keep construction activitie within normal working hou